

Scope of Work/Terms and Conditions

During Upgradation:

1. Upgradation of Ropeways should include:
 - I. Checking of Ropeways Alignment.
 - II. Ultrasonic test of carriage , main shaft, base of trestles and all other critical items;
 - III. Structural strength analysis of trestles & cabins;
 - IV. Upgradation of electrical system including control panel & Drive with proper safety features including automated braking system, limits and switches;
 - V. NDT of all rotating parts;
 - VI. NDT of civil foundation;
 - VII. Ultrasonic tests of Track Rope;
 - VIII. Earthing of complete system and building(lower station and upper station) with lightning arrestor;
 - IX. Testing of Track Rope and Haulage Rope;
 - X. Track Rope Shifting;
 - XI. Arrangement of auxiliary system during emergency conditions/failure of main system;
 - XII. Modernization of communication system between lower and upper stations;
 - XIII. Checking of liners of carriage and line sheaves;
 - XIV. Overhauling of motor, gear box and checking the condition of gear teeth.
2. Annual maintenance of Complete Ropeway plant for 10 years will be given to the contractor at Rs 2.5 lakhs per year(inclusive of all taxes).
3. Bidder should provide its complete project report/ manifesto including specifications, separate costing of all above tests and upgradation along with its models and versions. All drawings, specifications and/or other relevant documents describing the project should be provided to KMVN along with the technical bid of the document.
4. Details in regard to warranty of each supplied item shall be provided to KMVN along with the technical bid of the proposal.
5. The work should be completed in set period of time i.e., 45 days from the date of issue of work order.
6. Boarding/Lodging/Transport expenses of workers and technical staff of bidder should be borne by the bidder itself.
7. KMVN,Nainital shall not be responsible for any misshappening/casualty/accident during upgradation of Ropeway,Nainital.
8. Contractor should provide training/guidelines to Ropeway persons during upgradation work.

After Upgradation:

1. List of all Mechanical/ Electrical/Electronic Parts in Ropeway should be provided with their specifications and locations to KMVN.
 2. 1 set of spare parts of Control Panel/and or other devices; wherever required should be made available to KMVN free of cost.
 3. Basic Maintenance manual to be given to KMVN.
 4. Daily, Weekly, Bi-Monthly, Monthly, Half Yearly, Annually, Five Yearly Maintenance check List to be provided.
 5. Certificate stating that 'Ropeway,Nainital is safe for passenger operation ' should be provided by the contractor.
 6. Contractor Technical Person should stay in Ropeway, Nainital for atleast 01 month after upgradation as if there will be need or problem during passenger operation.
 7. Certificate for Life of Ropeway after modification should be provided to KMVN,Nainital.
 8. Certificate of warranty period of upgradation work (minimum 05 years) should be provided to KMVN,Nainital.
 9. Monthly meeting with KMVN team till one year to discuss about the issues/betterment if any.
 10. List of Suppliers of Spare parts to be shared with KMVN,Nainital so that it can be easily available when needed or to maintain inventory.
 11. Inspection of Ropeway should be done by contracting team every month till one year .
 12. In case of any emergency, Contractor person should be called anytime and needs to present at Ropeway with 12 hours.
- ***Note - That the expenses of execution and registration including the stamp duty and the registration fee, shall be borne by the bidder.

रोपवे नैनीताल के सभी इलैक्टिकल/इलैक्ट्रानिक्स/मैकेनिकल पार्टस एवं सिविल कार्यों की टैस्टिंग, मरम्मत, बदलने एवं आधुनिकीकरण किये जाने हेतु निविदा प्रपत्र

तकनीकी निविदा फार्म

- 1- निविदादाता का नाम :
- 2- पिता का नाम:
- 3- फर्म का नाम:
- 4- पता:
- 5- दूरभाष:
- 6- ईमेल आईडी:
- 7- पैन कार्ड संख्या(प्रति संलग्न करें) :
- 8- जीएसटी रजिस्ट्रेशन संख्या (प्रति संलग्न करें) :
- 9- फार्म क्रय की रसीद संख्या(मूल में संलग्न करें)
- 10- धरोहर राशि रू0 5 लाख के एफ.डी.आर. का विवरण (प्रबन्ध निदेशक कुमाऊँ मण्डल विकास निगम के नाम बन्धक होगी) मूल में संलग्न:
- 11- रू0 100/- का नॉन ज्यूडिशियल स्टाम्प पेपर मय हस्ताक्षरयुक्त रू0 1.00 के रेवेन्यू टिकट के साथ निविदा के तकनीकी भाग के साथ संलग्न करना अनिवार्य होगा ।
- 12- प्रोजेक्ट की विस्तृत रिपोर्ट (निविदा की तकनीकी भाग के साथ संलग्न करें)

निविदाकार के हस्ताक्षर-

नाम-

पता-

रोपवे नैनीताल के सभी इलैक्टिकल/इलैक्ट्रानिक्स/मैकेनिकल पार्टस एवं सिविल कार्यों की टैस्टिंग, मरम्मत, बदलने एवं आधुनिकीकरण किये जाने हेतु निविदा प्रपत्र

वित्तीय निविदा फार्म

निविदादाता का नाम:-

प्रस्तावित धनराशि :-लाख + 18 प्रतिशत जीएसटी
प्रस्तावित धनराशि (अंको में) :-

उपरोक्त कार्यों की अधिकतम धनराशि निगम द्वारा रू0 150 लाख (रू0 एक करोड़ पचास लाख मात्र)+जी0एस0टी0 निर्धारित की गई है । इस धनराशि से न्यूनतम धनराशि अंकित किये जाने वाले निविदादाता की निविदा स्वीकार की जायेगी ।

निविदाकार के हस्ताक्षर-

नाम-

पता-